

18,900 LITRE PRECAST WASTEWATER HOLDING TANK MODEL H19H

WILKINSON HEAVY PRECAST LIMITED

DUNDAS, ONTARIO

905-628-5611

www.wilkinsonheavyprecast.com

CLASS H - HEAVY CONSTRUCTION

CONSTRUCTION DETAILS *

Concrete: 35 MPa at 28 Days, 5 to 8% Air Entrainment.


Reinforcing: 15 M bars at 300 mm centres each way in walls, floor and roof.
Eight extra 15 M bars around roof access opening.
Minimum cover over reinforcing steel - 25 mm.

Weight: Top Section 15,900 kg
Bottom Section 15,900 kg
Total 31,800 kg

Actual Capacity: 9432 Litres Per Vertical Metre.
18,864 Litres to Underside of Roof Slab.

NOTES

1. Large 685 mm diameter roof access openings facilitate tank maintenance. Unless otherwise specified/ordered this tank will be shipped with 840 mm diameter concrete hatch covers. Please note that each cover weighs approximately 125 kg and must be handled only with suitable mechanical lifting equipment. Please see Access Riser section for available options.
 2. Close tolerance of tongue and groove joint and fibrous mastic sealant ensures a solid structural and watertight seal. Primer and Mastic Band are supplied with each tank for application to the external surface of the tank over the joint between sections. This band is to be applied by the installing contractor.
 3. Number, size and positioning of wall penetrations to customer's specification.
 4. Top section lifting points four places.
 5. Bottom section lifting points four places.
- This tank is available with aluminum ladder to the floor. Consult with the factory as to how this will affect the size and location



* Commensurate with a 4 Metre burial over the top slab in firm soil. This tank is designed for burial in areas of vehicular traffic

For recommended installation procedures refer to Wilkinson Installation Guidelines and Lifting and Assembly Instructions.

WARNING ! IMPROPER INSTALLATION ESPECIALLY IN UNSTABLE SOILS CAN RESULT IN THE STRUCTURAL FAILURE OF THIS PRODUCT